8612 Eagle Creek Parkway, Savage, MN 55378
Tel: (952) 746-5880 ◆ Fax: (952) 746-5882
Mailbox@FieldConsultingInc.com
www.FieldConsultingInc.com

March 26, 2019

ISD# 834 1875 Greely Street South Stillwater, MN 55082 Attn: Mr. Tony Willger

RE: Radon Sampling

Site: Oak-Land Middle School

Field Environmental Consulting, Inc. (FIELD ENVIRONMENTAL) appreciates the opportunity to provide results for radon monitoring conducted at Oak-Land Middle School.

Radon levels are measured in picocuries per liter or pCi/L. The Environmental Protection Agency (EPA) and the Minnesota Department of Health (MDH) action level for indoor radon is 4.0 pCi/L.

Radon monitoring was conducted using AccuStar® PicoCan 275 short-term open face charcoal canisters (registered device #AC-6048).

In February 2019, eighty-nine (89) detectors were analyzed for radon concentration. All samples were below the action level of 4.0 pCi/L. No additional action necessary.

PREPARED and REVIEWED BY:

Field Environmental Consulting, Inc.

Amy Weinzierl (CSP #27824)

Amy Weingel

EHS Manager / Licensed Radon Measurement Professional (RMEA-00111)

amy@fieldconsultinginc.com

952-746-5880



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 19036

Field Environmental Consulting, Inc. 8612 Eagle Creek Parkway
Savage MN 55378

Oak Land Middle 820 Manning Ave N Lake Elmo MN 55042

| Log Number | Device Number | | Test Expo | sure Duratio | n: | Area Tested | Result pCi/L |
|---------------|------------------|------------|-----------|--------------|---------|--|-----------------|
| 3219461 | 3945282 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Cust. Office Locker Top Rear | < 0.4 |
| 3219462 | 3945343 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Cust. Office Locker Top Rear Duplicate | < 0.4 |
| 3219463 | 3945406 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Boy Locker Room Office Microwave | 1.2 |
| 3219464 | 3945283 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Room Café D111 Audio | < 0.4 |
| 3219465 | 3945281 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Room Café D111 Gatorade Top | 0.4 |
| 3219466 | 3945277 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Room Staff Lounge 149 Fridge Top | 0.5 |
| 3219467 | 3945279 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Room 148 Tall Cab Top | < 0.4 |
| 3219468 | 3945276 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Room 147 Cab Behind Frog | < 0.4 |
| 3219469 | 3945280 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Room Office 141 Trophies | 0.7 |
| 3219470 | 3945278 | 02/18/2019 | 6:20 am | 02/21/2019 | 6:25 am | First Floor Room 143 Tall Cab Top | 0.4 |
| 3219471 | 3945274 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 147 Office Stuffed Animal Shelf | < 0.4 |

Test Performed By: Amy Weinzierl Certification Number: RMEA-00111

Distributed by: Field Environmental Consulting, Inc.

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 19036

Field Environmental Consulting, Inc. 8612 Eagle Creek Parkway Savage MN 55378 Oak Land Middle 820 Manning Ave N Lake Elmo MN 55042

| Log Number | Device Number | | Test Expo | sure Duratio | on: | Area Tested | Result pCi/L |
|---------------|------------------|------------|-----------|--------------|---------|--|-----------------|
| 3219472 | 3945273 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 135 Tall Cab Top | < 0.4 |
| 3219473 | 3945272 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 136 Tall Cab Top | 0.7 |
| 3219474 | 3945275 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 110A Tall Cab Top | < 0.4 |
| 3219475 | 3945271 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 110A Tall Cab Top Duplicate | < 0.4 |
| 3219476 | 3945284 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 108A Tall Cab Top | 0.8 |
| 3219477 | 3945286 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 107A Tall Cab Top | < 0.4 |
| 3219478 | 3945285 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 106A Fridge Top | < 0.4 |
| 3219479 | 3945287 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 113A Grey File Cab Back | 0.4 |
| 3219480 | 3945288 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:45 am | First Floor Room 105A Tall Cab Top | < 0.4 |
| 3219481 | 3945289 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room 104A Tall Cab Top | < 0.4 |
| 3219482 | 3945290 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room 103A Tall Cab Top | 0.5 |

Test Performed By: Amy Weinzierl Certification Number: RMEA-00111

Distributed by: Field Environmental Consulting, Inc.

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.



EPA Method #402-R-92-004 **Charcoal Canister** NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 19036

Field Environmental Consulting, Inc. 8612 Eagle Creek Parkway Savage MN 55378

Oak Land Middle 820 Manning Ave N Lake Elmo MN 55042

| Log Number | Device Number | | Test Expo | sure Duratio | on: | Area Tested | Result pCi/L |
|---------------|------------------|------------|-----------|--------------|---------|--|-----------------|
| 3219483 | 3945211 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room 103A Tall Cab Top Duplicate | 0.7 |
| 3219484 | 3945212 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room 102A Tabll Cab Top | < 0.4 |
| 3219485 | 3945213 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room 101A Tall Cab Top | 0.4 |
| 3219486 | 3945214 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room Nurse Cab Shelf | < 0.4 |
| 3219487 | 3945216 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room Nurse Office Tall Cab | < 0.4 |
| 3219488 | 3945215 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room Mrs. Osberg Black Cab | 0.4 |
| 3219489 | 3945219 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room Mrs. Coe Painting | 0.5 |
| 3219490 | 3945220 | 02/18/2019 | 7:05 am | 02/21/2019 | 7:00 am | First Floor Room Mrs. Goetz Mugs | < 0.4 |
| 3219491 | 3945221 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Room Mrs. Zilles Shelf | < 0.4 |
| 3219492 | 3945222 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Room Mrs. Adamle KU Bear | 0.4 |
| 3219493 | 3945223 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Room Mrs. Collins Grey Top Cab | < 0.4 |

Test Performed By: Amy Weinzierl Certification Number: RMEA-00111

Distributed by: Field Environmental Consulting, Inc.

Date Received: 02/26/2019 02/26/2019 Date Analyzed: 02/27/2019 Date Reported: 02/28/2019 Date Logged:

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Oak Land Middle

Property Tested: Project # 19036

Field Environmental Consulting, Inc. 8612 Eagle Creek Parkway Savage MN 55378

Lake Elmo MN 55042

820 Manning Ave N

| Log Number | Device Number | | Test Expo | sure Duratio | on: | Area Tested | Result pCi/L |
|---------------|------------------|------------|-----------|--------------|---------|--|-----------------|
| 3219494 | 3945224 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Room Mrs. Fields Behind Frame | < 0.4 |
| 3219495 | 3945225 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Room Mr. Kane Behind Frame | 0.4 |
| 3219496 | 3945226 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Room Deputy Plant | 0.6 |
| 3219497 | 3945228 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Main Office Behind Frame | < 0.4 |
| 3219498 | 3945227 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Main Office Behind Frame Duplicate | < 0.4 |
| 3219499 | 3945229 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Room Computer Lab Trophy | 0.4 |
| 3219500 | 3945230 | 02/18/2019 | 7:20 am | 02/21/2019 | 7:10 am | First Floor Room Compjuter Lab Office Wire Shelf | 0.6 |
| 3219501 | 3945218 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room Media Center Read Box Shelf | 8.0 |
| 3219502 | 3945217 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room Media Center Printer | 8.0 |
| 3219503 | 3945158 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room 101A Tall Cab Shelf | < 0.4 |
| 3219504 | 3945159 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room 102B Tall Cab Shelf | < 0.4 |

Test Performed By: Amy Weinzierl Certification Number: RMEA-00111

Distributed by: Field Environmental Consulting, Inc.

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for: Property Tested: Project # 19036

Field Environmental Consulting, Inc.

Oak Land Middle

8612 Eagle Creek Parkway

820 Manning Ave N

Savage MN 55378

Lake Elmo MN 55042

| Log Number | Device Number | | Test Expo | osure Duratio | on: | Area Tested | Result pCi/L |
|---------------|------------------|------------|-----------|---------------|---------|--|-----------------|
| 3219505 | 3945160 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room 103B Tall Cab Shelf | < 0.4 |
| 3219506 | 3945156 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room 104B File Cab | < 0.4 |
| 3219507 | 3945157 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room 105B Tall Cab Shelf | < 0.4 |
| 3219508 | 3941470 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room 114B Lamp | < 0.4 |
| 3219509 | 3941546 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room 113B Lamp | < 0.4 |
| 3219510 | 3931403 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:25 am | First Floor Room 106B Shelf | < 0.4 |
| 3219511 | 3941548 | 02/18/2019 | 8:00 am | 02/21/2019 | 7:30 am | First Floor Room 107B Speaker | < 0.4 |
| 3219512 | 3931401 | 02/18/2019 | 8:00 am | 02/21/2019 | 7:30 am | First Floor Room 108B Tall Cab Shelf | < 0.4 |
| 3219513 | 3941541 | 02/18/2019 | 8:00 am | 02/21/2019 | 7:30 am | First Floor Room 108B Tall Cab Shelf Duplicate | 0.7 |
| 3219514 | 3931310 | 02/18/2019 | 8:00 am | 02/21/2019 | 7:30 am | First Floor Room 110B Tall Cab Shelf | 1.1 |
| 3219515 | 3931404 | 02/18/2019 | 8:00 am | 02/21/2019 | 7:30 am | First Floor Room Auditorium Light Right | 2.5 |

Test Performed By: Amy Weinzierl Certification Number: RMEA-00111

Distributed by: Field Environmental Consulting, Inc.

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for: Property Tested: Project # 19036

Field Environmental Consulting, Inc.

Oak Land Middle

8612 Eagle Creek Parkway

Savage MN 55378

Lake Elmo MN 55042

| Log Number | Device Number | | Test Expo | osure Duratio | on: | Area Tested | Result pCi/L |
|---------------|------------------|------------|-----------|---------------|---------|--|-----------------|
| 3219516 | 3931405 | 02/18/2019 | 8:00 am | 02/21/2019 | 7:30 am | First Floor Room Auditorium Light Right | 1.7 |
| 3219517 | 3931492 | 02/18/2019 | 8:00 am | 02/21/2019 | 7:30 am | First Floor Room Gym Above Mat | < 0.4 |
| 3219518 | 3941547 | 02/18/2019 | 8:00 am | 02/21/2019 | 7:30 am | First Floor Room Gym Above Mat | 0.5 |
| 3219519 | 3945350 | 02/18/2019 | 8:00 am | 02/21/2019 | 7:30 am | First Floor Room Gym Above Mat Field Blank | < 0.4 |
| 3219520 | 3945411 | 02/18/2019 | 6:30 am | 02/21/2019 | 6:30 am | First Floor Room 130D Top of Tall Cabinet | 0.5 |
| 3219521 | 3945420 | 02/18/2019 | 6:30 am | 02/21/2019 | 6:30 am | First Floor 134D Top of Cab above Sink | 0.4 |
| 3219522 | 3945418 | 02/18/2019 | 6:30 am | 02/21/2019 | 6:30 am | First Floor 134D Top of Cab above Sink Duplicate | 0.7 |
| 3219523 | 3945417 | 02/18/2019 | 6:40 am | 02/21/2019 | 6:30 am | First Floor Room 135D Top of Tall Cabinet | 0.7 |
| 3219524 | 3945393 | 02/18/2019 | 6:40 am | 02/21/2019 | 6:30 am | First Floor Room 138D Top of Tall Cabinet NE | 0.5 |
| 3219525 | 3945416 | 02/18/2019 | 6:40 am | 02/21/2019 | 6:30 am | First Floor Room 140D Top of Cabinet N Side | 0.5 |
| 3219526 | 3945402 | 02/18/2019 | 6:50 am | 02/21/2019 | 6:30 am | First Floor Room 142D Top of Cabinet | 1.2 |

Test Performed By: Amy Weinzierl Certification Number: RMEA-00111

Distributed by: Field Environmental Consulting, Inc.

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 19036

Field Environmental Consulting, Inc. 8612 Eagle Creek Parkway Savage MN 55378 Oak Land Middle 820 Manning Ave N Lake Elmo MN 55042

| Log Number | Device Number | | Test Expo | sure Duratio | on: | Area Tested | Result pCi/L |
|---------------|------------------|------------|-----------|--------------|---------|--|-----------------|
| 3219527 | 3945415 | 02/18/2019 | 7:00 am | 02/21/2019 | 6:30 am | First Floor Room 197 Top of Speaker | < 0.4 |
| 3219528 | 3945392 | 02/18/2019 | 7:00 am | 02/21/2019 | 6:30 am | First Floor Room 195 Top of Tall Cabinet | < 0.4 |
| 3219529 | 3945396 | 02/18/2019 | 7:00 am | 02/21/2019 | 6:30 am | First Floorf Room 193 Top of Cabinet by Door | < 0.4 |
| 3219530 | 3945401 | 02/18/2019 | 7:10 am | 02/21/2019 | 6:45 am | First Floor Room 140C Speaker Shelf SE Side | 0.4 |
| 3219531 | 3945414 | 02/18/2019 | 7:10 am | 02/21/2019 | 6:45 am | First Floor 140C Office Top of Bookshelf | 0.5 |
| 3219532 | 3945412 | 02/18/2019 | 7:10 am | 02/21/2019 | 6:45 am | First Floor 140C Office Top of Bookshelf Duplicate | 0.4 |
| 3219533 | 3945394 | 02/18/2019 | 7:20 am | 02/21/2019 | 6:45 am | First Floor Room 135C Top of Cabinet N Side | 1.5 |
| 3219534 | 3945403 | 02/18/2019 | 7:20 am | 02/21/2019 | 6:45 am | First Floor Room 135C Office Top of Display Case | 0.8 |
| 3219535 | 3945404 | 02/18/2019 | 7:20 am | 02/21/2019 | 6:45 am | First Floor Room 130C Top of Tall Cabinet | 0.8 |
| 3219536 | 3945407 | 02/18/2019 | 7:20 am | 02/21/2019 | 6:45 am | First Floor Room 116C Top of Tall Cabinets | 0.5 |
| 3219537 | 3945409 | 02/18/2019 | 7:20 am | 02/21/2019 | 6:45 am | First Floor Room 120C Top of Tall Cabinet | 0.4 |

Test Performed By: Amy Weinzierl Certification Number: RMEA-00111

Distributed by: Field Environmental Consulting, Inc.

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 19036

Field Environmental Consulting, Inc. 8612 Eagle Creek Parkway Savage MN 55378 Oak Land Middle 820 Manning Ave N Lake Elmo MN 55042

| Log Number | Device Number | | Test Expo | sure Duratio | on: | Area Tested | Result pCi/L |
|---------------|------------------|------------|-----------|--------------|---------|--|-----------------|
| 3219538 | 3945410 | 02/18/2019 | 7:30 am | 02/21/2019 | 6:45 am | First Floor Room 119C Top of Tall Cabinet NW | < 0.4 |
| 3219539 | 3945413 | 02/18/2019 | 7:30 am | 02/21/2019 | 6:45 am | First Floor Room 117C Top of Tall Cabinet | 0.7 |
| 3219540 | 3945405 | 02/18/2019 | 7:30 am | 02/21/2019 | 7:00 am | First Floor 118C Top of Tall Cabinet | < 0.4 |
| 3219541 | 3945408 | 02/18/2019 | 7:30 am | 02/21/2019 | 7:00 am | First Floor 118C Top of Tall Cabinet Duplicate | < 0.4 |
| 3219542 | 3945397 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:00 am | First Floor Room 115C Top of Tall Cabinet | 0.9 |
| 3219543 | 3945399 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:00 am | First Floor Room 114C Top of Tall Cabinet | < 0.4 |
| 3219544 | 3945419 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:00 am | First Floor Room 113C Top of Tall Cabinet | < 0.4 |
| 3219545 | 3945400 | 02/18/2019 | 7:40 am | 02/21/2019 | 7:00 am | First Floor 112C Top of Upper Cabinet W Wall | < 0.4 |
| 3219546 | 3945398 | 02/18/2019 | 7:50 am | 02/21/2019 | 7:00 am | First Floor Room 111C Top of Tall Cabinet | < 0.4 |
| 3219547 | 3945345 | 02/18/2019 | 7:50 am | 02/21/2019 | 7:00 am | First Floor Room 108C Top of Upper Cabinet | < 0.4 |
| 3219548 | 3945349 | 02/18/2019 | 7:50 am | 02/21/2019 | 7:00 am | First Floor Room 183 Top of Tall Cabinet by Desk | 0.8 |

Test Performed By: Amy Weinzierl Certification Number: RMEA-00111

Distributed by: Field Environmental Consulting, Inc.

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for: Property Tested: Project # 19036

Field Environmental Consulting, Inc.

Oak Land Middle

8612 Eagle Creek Parkway

Savage MN 55378

Lake Elmo MN 55042

 Log
 Device Number
 Test Exposure Duration:
 Area Tested
 Result pCi/L

 3219549
 3945344
 02/18/2019
 7:50 am
 02/21/2019
 7:00 am
 First Floor Room 186 Top of Tall Cabinet by Desk
 < 0.4</td>

Test Performed By: Amy Weinzierl Certification Number: RMEA-00111

Distributed by: Field Environmental Consulting, Inc.

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

Oak-Land Middle School Short-Term Radon Monitoring Project #19036





